# Passive Treatment of Mining Influenced Water: From Bench Scale to O & M





#### BIOCHEMICAL REACTOR CONSTRUCTION, MINE POOL CHEMISTRY CHANGES, & O & M GOLINSKY MINE, CALIFORNIA

Jim Gusek, Sovereign Consulting Inc., and Rick Weaver, US Dept. of Agriculture, Forest Service






#### **Golinsky Mine, Trinity National Forest**




- I. BCR Design & Construction
- II. Mine Pool Improvements
- III. Operation & Maintenance



## **Site Location & Project History**

#### Site/Project History

- Mine Operates 1904 to 1938 (copper & gold)
- USFS acquires property in 1944 through purchase
- 2004 Bench Test Construction & Operation
- □ 2004 Design/build buried pipeline
- 2004 2006 Pilot Scale Construction & Operation
- □ 2006 Pilot decommissioning
- 2007 Full Scale Module 1 Design
- 2010 Full Scale Construction
- 2011 Full Scale Start-up
- 2012-2016 Vicinity Drought
- 2016 O&M Activity



# **Bench Test & Pilot Test Setup**







17 Weeks Bench Flow Range:

8.5 to 16.4 Liters/day

Pilot Average Flow:

0.9 gpm

### Mine Water Chemistry – Pilot Testing

# **Influent Water (Lower Portal)**

pH - 2.7

Fe – 73 mg/L

Al - 23 mg/L

Mn - 0.85 mg/L

Zn - 37 mg/L

Cu - 12 mg/L

 $Ni - 0.031 \, mg/L$ 

Cd - 0.47mg/L

 $SO_4 - 664 \text{ mg/L}$ 

#### Pilot BCR Effluent

pH - 7.2

Fe - 0.8 mg/L

AI - 0.06 mg/L

Mn - 2.5 mg/L

Zn - 0.1 mg/L

Cu - < 0.003 mg/L

Ni - 0.007mg/L

 $Cd - 0.006 \, mg/L$ 

 $SO_4 - 488 \text{ mg/L}$ 

#### **Passive Treatment Chemistry 101**

$$SO_4^{-2} + 2 CH_2O$$
 $HS^- + 2HCO_3^- + H^+$ 
(Sulfate reduction and neutralization by bacteria)

REDUCING/
ANAEROBIC
CONDITIONS

 $Zn^{+2} + HS^- \leftarrow ZnS(s) + H^+$ 
(Sulfide precipitation)

$$Fe^{+3} + 3 H_2O$$
 Fe(OH)<sub>3</sub>(s) + 3 H<sup>+</sup>

(Hydroxide precipitation)

# **Module 1 Design Chemistry**

Parameter	Lower Portal Estimate for Design (2007 data)	Lower Portal (Pilot average for 27 months - 2004 to 2006)
Flow, L/min	37.8	3.6
Flow, gpm	10	0.9
pH S.U.	3.0	2.7
Fe, mg/L	27	73
Cu, mg/L	14	12
Zn, mg/L	67	37
Cd, mg/L	0.73	0.47
Al, mg/L	31	23
Mn, mg/L	0.42	0.85
Sulfate mg/L	<500	664

# Mine, Pipeline, and Abandoned Limestone Quarry







## Phased Module Implementation

- Portal flow data suggests peak of 90 gpm during wet months
- No available space at the mine site itself
- Available space at the quarry only has room for 30 gpm
- Site access is restricted; it's difficult to build full PTS capacity in a single construction season
- Limited funding supports design of 10 gpm "starter" module and monitor to see if addition modules are necessary

## **Overall Design Philosophy**

- All flows by gravity
- Biochemical reactor sized for 10 gpm / 38 liters minute
- Any by-passed flow (>10 gpm) would be neutralized by treated water in a mixing pond
- Mixing pond effluent would be infiltrated into native ground in a "Flow Dispersion Zone"
- "Tweak" substrate recipe based on experience at other sites

#### **BCR Substrate Modification**

Component	Pilot BCR	Full BCR
Rice Hulls	10%	10%
Wood Chips	40%	50%
Hay	10%	10%
Limestone	30%	30%
Manure <sup>1</sup>	10%	<0.1%

Manure (and 6 cy of depleted pilot substrate) rototilled into upper 12 inches of substrate

## **Construction Challenges**

- Lake levels are the lowest in years due to drought
  - Good news: mobilization site close to Shasta Dam (2.4 miles from beach head)
  - Bad news: off-loading barges will be difficult on sloping shore at beach head
- Drought ends from El Nina rains as bid walk is conducted (March 2010)
- Lake levels rise, and rise, and rise some more...
- Preferred mobilization site is submerged; alternate site is 6.9 miles from beach head




# Lake level recovery: too much of a good thing



Initial Contractor Mobilization Site (2.4 miles)


# **Construction Challenges (Continued)**

• Storing materials at a very constricted site



# **Construction Challenges (Continued)**

 Ground conditions in one corner of the quarry require field modification




BCR Footprint reduced by 3.6%

# **Construction Challenges (Continued)**

- Delayed start due to weather and storm water BMP's puts project behind schedule and reduced available construction budget
- Ground conditions in the mixing pond footprint spook contractor
- Mixing pond is dropped from the contractor's work scope (see paper [Gusek, 2011] for details)
- Flow Dispersion Zone design is modified to minimize imported riprap

# Golinsky BCR Construction, 2010 (with ARRA Funding)









Construction Cost: \$1.3 million (about \$0.012 per gallon for 20-yr life)

# Final BCR As Built (January, 2011)



# BCR Module 1 Commissioning Challenges

- Portal 3 is the only mine pool plumbed into the quarry when the BCR is ready for commissioning (we used it for soil moisture, dust control)
- Portal 3 sulfate concentration is only 8 to 10 mg/L
- Lower Portal pipeline is plugged with iron precipitates;
- Inclement weather prevented LP maintenance and the BCR filled with rain water

#### **Solutions**

- Added 20 lbs or 9.1 kg of Epsom salt to BCR inflow
- Added a 30 lbs or 13.4 kg "teabag" of agricultural gypsum to flow distribution vault
- Influent sulfate 14 mg/L; effluent 4 mg/L
- Lower Portal plumbed in January 25<sup>th</sup> 2011, no "transition" (sulfate @1,127 mg/L; pH 2.7)

# BCR Receiving Lower Portal MIW (May 2011)



# BCR Receiving Lower Portal MIW (October 12, 2016)




# BCR Results (6 Lower Portal MIW events)

Parameter	Influent	Effluent
рН	2.7 s.u.	6.45 s.u.
Iron	97.2 mg/L	6.1 mg/L
Aluminum	28.6 mg/L	0.03 mg/L
Copper	19.3 mg/L	0.005 mg/L
Zinc	40.0 mg/L	0.5 mg/L
Cadmium	0.40 mg/L	0.005 mg/L
Calcium	19 mg/L	206 mg/L
Manganese	0.6 mg/L	2.1 mg/L
Sulfate	728 mg/L	324 mg/L
ORP	354 mv	-217 mv


97% metal removal efficiency in May 2011

# PART II PORTAL 3 MINE POOL IMPROVEMENTS

# Full Scale Passive System Schematic Layout




#### Portal 3 and Lower/Upper Portal Proximity












2007





#### **Portal 3 Water Chemistry Improvements**



0.07 to 0.11 gpm of Lower Portal MIW satisfies metal load in Portal 3 based on sulfate, zinc, and copper


### Final Thoughts (Parts I & II)

- Construction Cost: \$1.3 million ARRA funding with supplementary USFS funds
- Seven year span from initial bench tests in late 2003 to startup in late 2010 – fully commissioned in June 2011
- Safety record exemplary for remote site, heat stress, multiple water crossings
- After five years, system appears to be performing as intended – no surprises (yet)
- No ill effects due to prolonged drought

#### **PART III**

#### **OPERATION & MAINTENANCE**


# 2011 & function as designed through



# In 2012 following dry season, flow data logger malfunctioning at BCR




## Equipment mobilized to site with Landing Craft





# Influence of vegetation potentially adversely affecting iron removal



### Mini excavator used to pull willows



# Mini excavator moving vegetation removed from BCR



### BCR after willow removal



# Repairing BMPs on access road using hand tools and mini excavator





# Clearing access road of vegetation





### Pipelines from Lower adit. Iron hydroxide sludge blockage





# Upper Adit Link Seal and Stainless Steel Flexible Coupling installed to repair leak & stabilize pipe at bulkhead





# Leak at Saddle Tee on Upper Adit Pipe Repairing Saddle Tee with Romax Clamp






# Trash bag stuck in pipe causing plug




### Lower Adit Bat Gate Sock Filter over Floor Drain





# Winter to summer flow rate decrease from 4.5 gpm to 1.5 gpm between April 25 and June 6, 2016. Estimated cumulative total of 233,000 gallons received by the BCR.



# Changing battery in data logger at BCR influent flume. Flow was 0.75 GPM on 10/12/16



# Pipes replaced due to excessive iron hydroxide deposition



BCR at low water level on October 16, 2016 at end of dry summer



### BCR on October 19, 2016 after 4 to 5 inches of rain in four days



#### Mass Removal Rates from Spring

Monitorina

Parameter	BCR Influent	BCR Effluent	Pounds Removed During Reporting Period	Pounds Removed per day During Reporting Period	Removal Efficiency During Reporting Period
Sulfate (mg/L)	1,400	1,500	See Note 1 Below		
Dissolved Aluminum (µg/L)	34,000	<50	66.1	1.57	100%
Dissolved Iron (µg/L)	85,000	150,000	See Note 2 Below		
Dissolved Cadmium (µg/L)	710	1.8	1.4	0.03	99.7%
Dissolved Copper (µg/L)	27,000	2.5	52.5	1.25	100%
Dissolved Manganese (µg/L)	920	3,300	See Note 2 Below		
Dissolved Zinc (µg/L)	76,000	13,000	122.5	2.92	83%

#### Notes:

- Increase in sulfate concentrations may be attributable to reduced biological activity (as a result of no flow to the BCR) and associated sulfate reduction. If this is the case, future samples events should see increased sulfate reduction.
- It is suspected that increased dissolved iron and manganese concentrations are the result of iron precipitate collecting in the discharge piping.

### **Conclusion of Spring Monitoring Report**

- Monitoring observations and data collected by ECM have concluded that the BCR is operating within design parameters and is effectively removing metals from mine impacted water.
- The BCR appears to be treating the mine drainage successfully and the efficiency of removal for aluminum, cadmium, and copper is close to 100%, with zinc near 83% removed.

### Are the exposure assumptions, toxicity data, cleanup levels, Removal Action Objectives used at the time of the removal action (RA) still valid?

- Reduce or eliminate the release of acidity and heavy metals from the Site to surface water and meet ARARs,
- Reduce or eliminate the release of acidity and heavy metals to from the Site to groundwater and meet ARARs, and
- Reduce or eliminate the potential for exposure to humans, aquatic and terrestrial biota from ingestion or direct contact with AMD and potentially contaminated aquatic life.

Data indicate that the BCR is effective at treating MIW at the design flow rate of 10 gpm. The exposure assumptions, toxicity data, cleanup levels, and RAOs used at the time of the RA are still valid & the BCR system that was installed is protective.

## Storm water runoff in swale only MIW discharged from site



#### **Final Thoughts**

- Phased design approach minimizes risk
- Bulkheading underground mine workings is not always a good idea (ARD is going to find its way out)
- Passive treatment is LOW maintenance, not NO maintenance
- Removal Action assumptions still valid; BCR system is protective
- Special thanks to:
  - Brad Shipley (ret.), USFS P.O. 2003? to 2016, and
  - ECM Consultants, the current site monitoring and O & M contractor

### **Questions/Discussion??**

